

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
13 December 2001 (13.12.2001)

PCT

(10) International Publication Number
WO 01/94128 A1

(51) International Patent Classification⁷: **B44C 1/22, 1/20**

(21) International Application Number: **PCT/EP01/02760**

(22) International Filing Date: **12 March 2001 (12.03.2001)**

(25) Filing Language: **English**

(26) Publication Language: **English**

(30) Priority Data:
PV 2000-2168 9 June 2000 (09.06.2000) **CZ**

(71) Applicant (for all designated States except US):
GLAVERBEL [BE/BE]; Chaussée de la Hulpe 166,
B-1170 Brussels (Watermael-Boitsfort) (BE).

(72) Inventors; and

(75) Inventors/Applicants (for US only): **PEK, Alexander**
[CZ/CZ]; Fuèkova stezka 2383, 415 01 Teplice (CZ). **SIP,**
Pavel [CZ/CZ]; Struinec 19, 589 00 direc nad Doubravou
(CZ). **STIPAN, Jaroslav** [CZ/CZ]; Kostomlatská 69, 17
53 Svitec (CZ).

(74) Agents: **FARMER, Guy** et al.; Glaverbel, Dept. Intellectual Property, Centre R. & D., Rue de l'Aurore 2, B-6040 Jumet (BE).

(81) Designated States (*national*): AE, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CR, CU, CZ, DE, DK, DM, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.


(84) Designated States (*regional*): Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, TR).

Published:

— with international search report

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: **METHOD OF PRODUCING PERMANENT IDENTIFICATION OF GLASS SEGMENTS**



(57) Abstract: Before heat treatment of a glass sheet, a layer of enamel paint is printed on at least one portion of the glass sheet (5), either by screen-printing or tampon-printing, in the form of at least one block (4), on which at least one laser beam is directed in such a way that it removes a layer of enamel paint at desired positions (7), thereby providing the glass sheet with specific immediate information and identification data relative to date, time and/or process equipment which are stocked in a computer database for at least three years.

WO 01/94128 A1

Method of producing permanent identification of glass segments

The invention relates to a method of producing permanent identification of glass sheets, especially of safety glass for vehicles comprising the steps of applying a mark of enamel paint on at least one portion of a surface of a glass sheet, heating the glass sheet and subsequently cooling the glass sheet.

5 Safety glass, such as automobile glass, may be marked with the name or the logo of the glass manufacturer, and/or, the name or logo of the automobile constructor. The marking may further comprise normalisation characteristics appropriate for the given type of safety glass and the date on which the glass was manufactured. This marking provides identification at a glance of the glass
10 manufacturer, and in some cases identification of the product and time of production, by which the manufacturer gives a guarantee of the quality and safety of the glass.

The capacity of highly automated and operative production lines, for example in the automotive industry, allows production on a mass scale of thousands of units of glass sheets per day and, in some cases, per hour. During one day, a
15 number of technological parameters may vary, for example during the heating, tempering or bending of the glass sheet and may cause, in the case of particular technological operations, significant differences in the characteristics of the manufactured glass sheet. It is therefore desirable to identify the precise moment at which the glass sheet is manufactured in order to determine the specific technological
20 and composition parameters associated with it.

Known marking methods may be used to provide a daily marking whereas their use to provide a marking including both the date and time of manufacture may be too long to achieve and could negatively affect the speed of production. This daily marking may be achieved on the glazing at the end of the
25 manufacturing process and before it is mounted in the vehicle.

One disadvantage of having a marking which includes only the date of manufacture

is that a great number of glazings mounted in different vehicles will have the same marking.

Another disadvantage of such a marking is that once the glazing is mounted in the vehicle, it may be impossible to trace the production line on which it was
5 manufactured and the parameters of production associated to it. These parameters are important since they may influence the chemical and physical characteristics of the glazing.

One of the consequence of these known marking methods is that a client who wishes to obtain the individual technological characteristics of its glazing may have to refer
10 back to the firm which provided the marking.

For the marking of automotive glass, sand-blasting may be used. For instance, European patent n° 647 504 describes the equipment for the marking of glass for vehicles by jet blasting of abrasive materials to create the layout of the selected parts of the surface of the glass. Sand-blasting is not currently used mainly
15 due to the high energy and time requirements of the process, and also because the surface of the glass may be damaged in the course of this process.

European patent n° 433 137 describes a method for permanent identification of a sheet of glass with applications for glazings mounted in vehicles. The identification mark is created on a glass sheet by causing interaction between an
20 organic ink and an enamel, for example in the form of a peripheral band, during heat treatment of the glass.

European patent n° 637 517 describes a laser marking, through a glass sheet, of a portion of a peripheral black enamel band at which the enamel is adhered into the vehicle body work.

25 At present, the most common method for marking automotive glass is silk-screen printing, during which, the required marks are applied on the surface of the glass before heat treatment with the aid of a screen-printing mesh. This method is fast and reliable but has the disadvantage of producing a large series of glazings without individual information of each glass sheet.

According to one aspect, the present invention provides a method for producing permanent identification of glass sheets as defined in Claim 1.

The method according to the present invention may be included in the production cycle and therefore may provide the glass sheet with individual
5 information directly related to production parameters, which information is specific of the glass sheet. For example, this information may be related to the chemical composition and physical characteristics of the glass sheet which it may be desirable to be able to trace once the glass is mounted in a vehicle.

According to another aspect, the present invention provides a method
10 for producing permanent identification of glass sheets as defined in Claim 2. The block of enamel paint destined to provide the permanent identification of the glass sheet may be printed simultaneously with the marking comprising the name of the glass manufacturer and/or normalisation characteristics of the glass. Both the regular mark and the permanent identification are spaced from the peripheral enamel band.

The method according to Claim 2 offers the advantage of using the
15 same enamel for both the regular mark and the permanent identification of the glass sheet in addition to requiring only a single step of printing for these two types of mark during the manufacturing process thereby affording optimum use of time. Moreover, by separating the regular mark and the permanent identification from the peripheral
20 enamel band, they both remain visible when the glass sheet is, for example, adhered to a vehicle body work.

Both methods according to Claims 1 and 2 may provide identification of the glass sheet at a glance.

The block of enamel paint may be rectangular or of any other suitable
25 shape.

Preferably, the enamel paint is a silk-screenable paint or a tampon-printing colour.

The present invention may be used to provide an unambiguous and individual marking of each glass sheet and a glass identification which is visible and
30 permanent.

The identification of one product with respect to another and its tracing in the course of a process, for example during production and assembling, is therefore facilitated.

5 The permanent identification according to the present invention may be used on all types of glass for vehicles and automobiles, for example laminated windscreen, rear windows, side windows and roof windows, without causing damage to the glass. Moreover, the permanent identification may increase the safety of the vehicle against theft.

10 Another advantage of the permanent identification according to the present invention is that it may be inserted into automated production of glass, without interrupting the speed of the production cycle.

A further advantage of the present invention is that production and variation of the screen-printing design may be used for various types of time marking. This also applies to the tampon or transfer printing design.

15 Preferably, the laser used to remove a layer of enamel paint from the original block of enamel paint is a high quality of beam TEM₀₀ having an output of 5 W and a density output of 1.3 kW.mm⁻² which is generated by a laser head Nd:YAG having a wavelength of 1.06 m⁻⁶, with a driving system of marking and description of the material, generally called longitudinally diode drawn laser. Alternatively, a laser
20 beam of type CO₂ with a wavelength of 10.6 m⁻⁶ or other laser beams. Both types of laser have the advantage of not damaging the surface of the glass. The laser will preferably be directed onto the block of enamel paint from the side of the glass sheet which carries the block of enamel paint, and not through the glass sheet from the other side of the glass sheet.

25 Another advantage of the present invention is the possibility of linking the directional control of the laser beam to a computer database which provides identification information for each glass sheet. This computer database may provide individual information allowing the immediate identification of the printing equipment used and/or any immediate data relative to the individual characteristics and
30 properties of the glass sheet, such as time data. This data may be presented in the

form of a code, for example a bar code, written, number, graphic or picture code or any combination of these. The printed information may be kept in the memory of the computer database for a period of at least 3 years, preferably of 5 years, thereby ensuring safe preservation of information and facilitating eventual complaint procedures from the client.

Preferably, before the glass sheet is sent to the automotive constructor, an additional bar code, having the same code number as the enamel bar code on the glass sheet, may be produced on a self adhesive label which will be attached to the glass sheet. When the constructor assembles the different glass sheets in the vehicle, the additional bar code is detached and added to the log book of the individual vehicle. This provides the advantage of facilitating the tracing by the constructor of the glass sheet on a particular vehicle.

The invention will now be described, by way of example only, with reference to the accompanying drawings in which :

Figure 1 shows a vehicle glass sheet (1) comprising a peripheral enamel band (2), a regular mark (3) and a block of enamel paint (4). The latter marking is spaced from the peripheral enamel band (2) in order to provide individual identification of the glass sheet at a glance, for example when the glass sheet is mounted in a vehicle. This may be particularly advantageous when using the marking for example to trace theft of the vehicle.

Figure 2a shows the rectangular block of enamel paint comprising the portion of glass sheet (5) and the enamel paint (6).

Figure 2b shows the block of enamel paint (4) after at least one laser beam has been directed and has removed at least part of a layer of enamel paint (6) at desired position (7).

In order to manufacture, for example, a marked transparent side window of a vehicle, the following steps may be carried out.

Firstly, a piece of flat glass is cut and ground at the edges to the appropriate shape and is washed.

Secondly, the glass is inserted in a positioning template in order to be in a required position for the printing step. The printing is achieved at part of the surface of the glass sheet, preferably a visible corner, which surface will be positioned towards the inside of the vehicle upon assembling of the glass. The printing may be achieved by silk-screen printing of enamel paint using a MARAFLEX 1-T 56M type mesh but alternative printing methods may also be used. The information printed by this method may comprise the name of the glass manufacturer and its logo, the type of glass sheet used, and information relative to the required normalisation tests confirming the safety parameters of the glass. A block of paint in the shape of a rectangle 30 mm wide by 10 mm high is simultaneously printed with this information and a laser beam is subsequently directed towards this block in such a way that it removes at least part of a layer of the block only at positions required to provide identification information specific to the glass sheet. The paint may be allowed to dry prior to the action of the laser beam. The laser beam removes the enamel paint from selected positions from the surface of the glass sheet, for example by evaporation or ablation, without damaging the surface of the glass. The time required for the laser to operate may depend upon the type of enamel, the adherence of the layer of enamel paint to the glass and on the size of the area to be removed. The laser beam is connected to a computer database which provides information for the operation of the laser beam itself and thus provides unambiguous and individual code for each glass sheet. The database preferably keeps the information in memory for a certain period of time which period is preferably of at least three years.

Finally, the marking on the glass sheet undergoes heat treatment which hardens the enamel paint and fuses it to the glass surface. This is preferably achieved during a subsequent bending, tempering, and/or any other treatment of the glass sheet.

The information printed may relate not only to the day of manufacture, but may additionally contain data regarding the hour, minute and/or seconds, and an identification number of the equipment by which the printing was executed. The information may additionally contain codes relative to the automated work place or

other graphic elements and marks, for example bar codes, or other codes with higher corresponding value than the bar codes, for example two-dimensional codes.

The present invention further relates to a glass sheet comprising a permanent identification marking which is located on at least one non-peripheral portion of the glass sheet and comprises individual information and identification data
5 of the glass sheet which comprise the date and the time of manufacture of the glass sheet.

The present invention also relates to a glass sheet comprising a peripheral enamel band and a permanent identification marking which is spaced from
10 the peripheral band and which marking comprises individual information and identification data of the glass sheet which comprise the date and the time of manufacture of the glass sheet.

The permanent identification is preferably a bar code which is advantageously produced by laser beam ablation or laser beam evaporation.

The glass sheet according to the present invention is preferably an
15 automotive glazing. The permanent identification of the glass sheets according to the present invention is designed for visible, individual and unambiguous identification of each unit of safety glass, especially for transport means, and everywhere where it is advantageous to mark glass such as road freight vehicles, for windows or doors of rail
20 transport, or, as the case may be, plane or automobile transport, or for other types of safety glass, such as safety doors, walls and windows.

CLAIMS

1. A method of producing permanent identification of glass sheets, especially of safety glass for vehicles comprising the steps of applying a mark of enamel paint on at least one portion of a surface of a glass sheet, heating the glass sheet and subsequently cooling the glass sheet, characterised in that before heating
5 the glass sheet (1) a layer of enamel paint in the form of at least one block (4) is printed on at least one non-peripheral portion of the glass sheet, and that at least one laser beam is subsequently directed on the block of enamel paint (4) in such a way that it removes at least part of a layer of enamel paint at desired positions (7) from the original block of enamel paint substantially down to the surface of the glass thereby
10 providing the glass sheet with individual information and identification data.

2. A method of producing permanent identification of glass sheets, especially of safety glass for vehicles comprising the steps of applying a mark of enamel paint on at least one portion of a surface of a glass sheet, heating the glass sheet and subsequently cooling the glass sheet, characterised in that the glass sheet
15 (1) comprises a peripheral band of enamel paint (2) and that spaced from it a regular mark (3), comprising the name of the glass manufacturer and/or normalisation characteristics, and a layer of enamel paint in the form of at least one block (4) are printed simultaneously on at least one portion of the glass sheet, and that at least one laser beam is subsequently directed on the block of enamel paint (4) in such a way
20 that it removes at least part of a layer of enamel paint at desired positions (7) from the original block of enamel paint substantially down to the surface of the glass thereby providing the glass sheet with individual information and identification data, and that the glass sheet is subsequently heated.

3. A method of producing permanent identification of glass sheets
25 according to any preceding claim, in which the enamel paint is a silk-screenable paint.

4. A method of producing permanent identification of glass sheets according to any of claims 1 and 2, in which the enamel paint is transfer printed.

5. A method of producing permanent identification of glass sheets according to any preceding claim, in which the laser is of Nd:YAG type drawn by diodes.

6. A method of producing permanent identification of glass sheets according to any of claims 1 to 4, in which the laser is of CO₂ type.

7. A method of producing permanent identification of glass sheets according to any preceding claim in which the directional control of the laser beam is linked to a computer database which provides identification information for each glass sheet.

8. A method of producing permanent identification of glass sheets according to claim 7, in which, the computer database provides immediate time data.

9. A method of producing permanent identification of glass sheets according to any of claims 7 and 8, in which the computer database provides immediate information identifying the laser printing equipment.

10. A method of producing permanent identification of glass sheets according to any of claims 7 to 9, in which, the computer database provides an immediate data characterising and/or specifying the properties of an individual printed glass sheet in the form of any kind of bar codes, written, number, graphic or picture codes or any combination of these.

11. A method of producing permanent identification of glass sheets according to any of claims 7 to 10, in which, the computer database keeps in its memory the printed information for a period of time of at least three years.

12. A method of producing permanent identification of glass sheets according to any preceding claim in which the laser beam is directed on the side of the glass sheet which comprises the block of enamel paint.

13. A method of producing permanent identification of glass sheets according to any preceding claim, in which the permanent identification comprises a bar code and in which an additional bar code is produced on a self adhesive label which is attached to the glass sheet.

14. A method of producing permanent identification of glass sheets according to claim 13, in which the additional bar code has a code number identical to the code number of the bar code of the permanent identification.

5 15. A glass sheet comprising a permanent identification characterised in that the permanent identification is located on at least one non-peripheral portion of the glass sheet and comprises individual information and identification data of the glass sheet which comprise the date and the time of manufacture of the glass sheet

10 16. A glass sheet comprising a permanent identification marking in which the glass sheet comprises a peripheral enamel band and that the permanent identification is spaced from the peripheral band and comprises individual information and identification data of the glass sheet which comprise the date and the time of manufacture of the glass sheet.

15 17. A glass sheet comprising a permanent identification marking according to any of claims 15 and 16 in which the permanent identification marking is a bar code.

18. A glass sheet comprising a permanent identification marking according to any of claims 15 to 17 in which the permanent identification marking is produced by laser ablation or laser evaporation.

20 19. A glass sheet comprising a permanent identification marking according to any of claims 15 to 18 in which the glass sheet is an automotive glazing.




FIGURE 1




FIGURE 2

INTERNATIONAL SEARCH REPORT

Intern. Application No
PCT/ 1/02760A. CLASSIFICATION OF SUBJECT MATTER
IPC 7 B44C1/22 B44C1/20

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 7 B44C

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

WPI Data, PAJ, EPO-Internal

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	EP 0 868 960 A (VTF IND SARL) 7 October 1998 (1998-10-07) column 2, line 3 - line 20 ----	1,2, 14-16
X	EP 0 637 517 A (SAINT GOBAIN VITRAGE) 8 February 1995 (1995-02-08) column 1, line 52 -column 3, line 5 ----	1,2, 14-16
A	DE 35 39 047 A (WAERMEGERAETE & ARMATURENWERK) 10 July 1986 (1986-07-10) the whole document ----	1,2, 14-16
A	US 5 030 551 A (HERREN FRITZ ET AL) 9 July 1991 (1991-07-09) column 1, line 52 -column 2, line 2 -----	1,2, 14-16

☐ Further documents are listed in the continuation of box C.☒ Patent family members are listed in annex.

* Special categories of cited documents:

- *A* document defining the general state of the art which is not considered to be of particular relevance
- *E* earlier document but published on or after the international filing date
- *L* document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
- *O* document referring to an oral disclosure, use, exhibition or other means
- *P* document published prior to the international filing date but later than the priority date claimed

- *T* later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
- *X* document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
- *Y* document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.
- *G* document member of the same patent family

Date of the actual completion of the international search

28 August 2001

Date of mailing of the international search report

12/09/2001

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax (+31-70) 340-3016

Authorized officer

Herrmann, J

INTERNATIONAL SEARCH REPORT

Information on patent family members

International Application No

PCT/EP 91/02760

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
EP 0868960 A	07-10-1998	FR 2760202 A DE 69800023 D DE 69800023 T ES 2138872 T	04-09-1998 28-10-1999 31-05-2000 16-01-2000
EP 0637517 A	08-02-1995	DE 4326314 A AT 152673 T DE 69403032 D DE 69403032 T ES 2104307 T	09-02-1995 15-05-1997 12-06-1997 20-11-1997 01-10-1997
DE 3539047 A	10-07-1986	FR 2575422 A GB 2169282 A,B HU 42009 A,B IT 1184033 B NL 8503201 A YU 198385 A	04-07-1986 09-07-1986 29-06-1987 22-10-1987 16-07-1986 30-04-1988
US 5030551 A	09-07-1991	DE 59002516 D EP 0391848 A JP 2289478 A	07-10-1993 10-10-1990 29-11-1990